



Test Report: LRS-1200-12

1200W Low Profile Economical Enclosed Type Power Supply

■ DESIGN VERIFY TEST

Output Function Test

Input Function Test

Protection Function Test

Control Function Test

Component Stress Test

■ SAFETY & E.M.C. TEST

Safety Test



E.M.C. Test

■ RELIABILITY TEST


ENVIRONMENT TEST

DESIGN VERIFY TEST

OUTPUT FUNCTION TEST




NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT
1	OUTPUT VOLTAGE ADJUST RANGE	CH1: 12 V~ 15V	I/P : 230 VAC O/P : MIN LOAD Ta : 25°C	11.62V~15.56V/230VAC
2	OUTPUT VOLTAGE TOLERANCE	V1: -1%~ +1 %	I/P: 180VAC /305VAC O/P:FULL/ MIN. LOAD Ta:25°C	V1: 0.08 % ~ +0.17%
3	LINE REGULATION	V1: -0.5%~ +0.5 %	I/P: 180VAC~ 305VAC O/P:FULL LOAD Ta:25°C	V1: 0.00%~ +0.17%
4	LOAD REGULATION	V1: -0.5%~ +0.5%	I/P: 230VAC O/P:FULL ~MIN LOAD Ta:25°C	V1: -0.08%~ +0.17%
5	OVER/UNDERSHOOT TEST	< ± 5%	I/P: 230VAC O/P:FULL LOAD Ta:25°C	2.5%
	RIPPLE & NOISE (Max)	V1: 200 mVp-p	I/P: 230 VAC O/P: MIN LOAD—FULL LOAD Ta:25°C	V1: 117 mVp-p / 100% load
	high frequency :  low frequency : 			
7	SET UP TIME(Max)	277VAC/1500ms 230VAC/1500ms	I/P : 277VAC I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	277VAC/ 616ms 230VAC/ 691ms
	INPUT=277VAC/60HZ @ FULL LOAD CH1 : Output Voltage CH2 : AC Input Voltage INPUT=230VAC/50HZ @ FULL LOAD CH1 : Output Voltage CH2 : AC Input Voltage			

8	RISE TIME (Max)	277VAC/70ms 230VAC/70ms	I/P : 277VAC I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	277VAC/ 27.4ms 230VAC/13 ms
	INPUT=277VAC/60HZ @ FULL LOAD CH1 : Output Voltage 		INPUT=230VAC/50HZ @ FULL LOAD CH1 : Output Voltage 	
9	HOLD UP TIME (Typ.)	277VAC/10ms 230VAC/10ms	I/P : 277VAC I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	277VAC/ 23.2ms 230VAC/ 17ms
	INPUT=277VAC/60HZ @ FULL LOAD CH1 : Output Voltage CH2 : AC Input Voltage 		INPUT=230VAC/50HZ @ FULL LOAD CH1 : Output Voltage CH2 : AC Input Voltage 	
10	DYNAMIC LOAD	V1: 1200mVp-p	I/P: 230VAC O/P: (1)FULL /50% LOAD 50%DUTY / 120HZ (2)FULL /50% LOAD 50%DUTY / 1KHZ Ta:25°C	394mVp-p 386mVp-p



INPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT
1	INPUT VOLTAGE RANGE	180VAC~305VAC 255VDC~ 431VDC	(1) I/P: TESTING O/P: FULL LOAD (2) I/P: DC TESTING (L: + N:-) O/P: FULL / 50% LOAD (3) I/P: DC TESTING (L: - N:+) O/P: FULL / 50% LOAD Ta:25°C I/P: LOW-LINE-3V=177 V HIGH-LINE+10V=315V O/P:FULL/MIN LOAD (PLEASE CHECK DERATING CURVE) ON: 30 Sec OFF: 30 Sec 10MIN (POWER ON/OFF NO DAMAGE)	(1) 177V~300V (2) 255 Vdc~ 431Vdc/FULL LOAD 255Vdc~431 Vdc/50% LOAD (3) 255Vdc~ 431Vdc/FULL LOAD 255Vdc~ 431Vdc/50% LOAD TEST:OK
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE	I/P:180 VAC ~305 VAC O/P:FULL~MIN LOAD Ta:25°C	TEST: OK
3	INPUT CURRENT (Typ.)	277V/ 5A 230V/ 7A	I/P : 277VAC I/P : 230VAC O/P : FULL LOAD Ta : 25°C	I =4.41A/ 277VAC I =5.24A/ 230VAC
4	LEAKAGE CURRENT	< 2mA / 277VAC < 7.07mA (Peak)/ 277 VAC < 2mA / 240 VAC < 7.07mA (Peak)/ 240 VAC	I/P : 277 VAC I/P : 240 VAC O/P : Min LOAD Ta : 25°C	277VAC L-FG : 0.347mA N-FG : 0.347 mA L-FG : 0.663mA(Peak) N-FG : 0.656mA(Peak) 240VAC: L-FG : 0.345mA N-FG : 0.347mA L-FG : 0.612mA(Peak) N-FG : 0.617mA(Peak)

5	EFFICIENCY(Typ.)	91%	I/P:230 VAC O/P:FULL LOAD Ta:25°C	91.89%
EFFICIENCY vs LOAD 				
6	INRUSH CURRENT(Typ.)	277V/75A 230V/60A COLD START	I/P : 277VAC I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	I =68A/ 277VAC T50=1724us/277VAC I =46A/ 230VAC T50=2020us/30VAC
INPUT=277VAC/50HZ @ FULL LOAD CH1: Input current CH2 : AC Input Voltage  INPUT=230VAC/50HZ @ FULL LOAD CH1: Input current CH2 : AC Input Voltage 				

PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT
1	OVER LOAD PROTECTION	Protection type: 1、Output power >105% rated for more than 5 seconds then shut down o/p voltage, re-power on to recover 2、Constant current limiting for output power >150% rated for more than 5 seconds and then shut down o/p voltage, re-power on to recover	I/P: 305VAC I/P: 230VAC I/P: 180VAC O/P:TESTING Ta:25°C	119.56%/ 305VAC 119.56%/ 230VAC 119.56%/180VAC Protection type: 1、Output power >105% rated for more than 5 seconds then shut down o/p voltage, re-power on to recover 2、Constant current limiting for output power >150% rated for more than 5 seconds and then shut down o/p voltage, re-power on to recover



2	OVER VOLTAGE PROTECTION	16V~20V	I/P: 305VAC I/P: 230VAC I/P: 180VAC O/P:MIN LOAD Ta:25°C	17.1V/ 305VAC 17.3V/ 230VAC 17.3V/ 180VAC Protection type: Shut down o/p voltage, re-power on to recover
3	OVER TEMPERATURE PROTECTION	NO DAMAGE	I/P: 305VAC I/P: 180VAC O/P:FULL LOAD	O.T.P. Active Protection type : Shut down o/p voltage, re-power on to recover

3	REMOTE SENSE	S+ / S- Compensate voltage drop on the load wiring up to 0.3V.	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	> 0.3 V
4	DC OK Signal	1. PSU ON 3.3V~5.6V 2. PSU OFF 0V~1V	I/P:230VAC O/P:FULL LOAD Ta:25°C	TEST : OK
5	FAN NOISE(Typ.)	Built-in intelligent fan speed control detect by PSU'S internal temperature		
		10% load with Ta=25°C	45dB	
		70% load with Ta=25°C	53dB	
		I/P:230VAC O/P:10%Load/70%Load Ta:25°C TEST : 43.81dB/10%load 50.44dB/70%load		

COMPONENT STRESS TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT
1	PWM Transistor (D to S) or (C to E) Peak Voltage	Q4 Rated 41A/ 600V	AC ON/OFF I/P:High-Line +3V =308V VDS: O/P: (1)Full Load (2)Output Short (3)Dynamic Load Full Load/ Min. Load 90%Duty/1KHz (4)Dynamic Load Full Load/ Min. Load 90%Duty/3KHz (5)Dynamic Load Full Load/ Min. Load 90%Duty/5KHz (6)Dynamic Load 100% Load/ Min. Load 50%Duty/120Hz (7)0%→400% Load. I/P:Low-Line -3V = 177V O/P: (1)Full Load (2)Output Short (3)Dynamic Load Full Load/ Min. Load 90%Duty/1KHz (4)Dynamic Load Full Load/ Min. Load 90%Duty/3KHz (5)Dynamic Load Full Load/ Min. Load 90%Duty/5KHz (6)Dynamic Load 100% Load/ Min. Load 50%Duty/120Hz (7)0%→400% Load. Ta:25°C	VDS: (1) 500V (2) 508V (3) 508V (4) 500V (5) 500V (6) 504V (7) 508V VDS: (1) 496V (2) 512V (3) 496V (4) 496V (5) 496V (6) 512V (7) 512V

2	P.F.C Transistor (D to S) or (C to E) Peak Voltage	Q1 Rated 41A/ 600V	I/P:High-Line +3V =308 V AC ON/OFF O/P: (1)Full Load (2)Output Short (3)Dynamic Load Full Load/ Min. Load 90%Duty/1KHz (4)Dynamic Load Full Load/ Min. Load 90%Duty/3KHz (5)Dynamic Load Full Load/ Min. Load 90%Duty/5KHz (6)Dynamic Load 100% Load/ Min. Load 50%Duty/120Hz (7)0%→400% Load. I/P:Low-Line -3V =177V AC ON/OFF O/P: (1)Full Load (2)Output Short (3)Dynamic Load Full Load/ Min. Load 90%Duty/1KHz (4)Dynamic Load Full Load/ Min. Load 90%Duty/3KHz (5)Dynamic Load Full Load/ Min. Load 90%Duty/5KHz (6)Dynamic Load 100% Load/ Min. Load 50%Duty/120Hz (7)0%→400% Load. Ta:25°C	VDS: (1)472V (2)460V (3)468V (4)472V (5)472V (6)464V (7)460V VDS: (1)472V (2)472V (3)468V (4)468V (5)468V (6)472V (7)472V
3	P.F.C DIODE	D3 Rated 10 A/ 650V	I/P:High-Line +3V =308 V AC ON/OFF O/P: (1)Full Load (2)Output Short (3)Dynamic Load Full Load/ Min. Load 90%Duty/5KHz (4)Dynamic Load 100% Load/ Min. Load 50%Duty/120Hz I/P:Low-Line -3V = 177V AC ON/OFF O/P: (1)Full Load (2)Output Short (3)Dynamic Load Full Load/ Min. Load 90%Duty/5KHz (4)Dynamic Load 100% Load/ Min. Load 50%Duty/120Hz Ta:25°C	(1) 448V (2) 444V (3) 448V (4) 448V (1) 448V (2) 448V (3) 448V (4) 456V

4	Diode Peak Voltage	Q100 Rated 130A/ 60V Q104 Rated 130A/ 60V	AC ON/OFF I/P:High-Line +3V =308V O/P: (1)Full Load (2)Output Short (3)Dynamic Load Full Load/ Min. Load 90%Duty/1KHz (4)Dynamic Load Full Load/ Min. Load 90%Duty/3KHz (5)Dynamic Load Full Load/ Min. Load 90%Duty/5KHz (6)Dynamic Load 100% Load/ Min. Load 50%Duty/120Hz (7)0%→400% Load. (8)NO LOAD Ta:25°C	Q100: VDS: (1) 42.1V (2) 16.2V (3) 43.0V (4) 42.6V (5) 43.0V (6) 53.1V (7) 52.3V (8) 37.8V Q104: VDS: (1) 43.8V (2) 16.7V (3) 47.0V (4) 46.2V (5) 46.2V (6) 53.5V (7) 52.3V (8) 38.2V
5	Input Capacitor Voltage	C5 Rated: 330μ/ 450 V Surge voltage: 500 V	I/P:High-Line +3V =308V O/P: (1)Full Load input on/off (2) Min load input on /Off (3)Full Load /Min load Change (4)Full load continue Ta:25°C	(1)440V (2)428V (3)448V (4)440V
6	Control IC Voltage Test	PWM IC U2 Rated 8.9 V~ 15.5 V PFC IC U1 Rated -0.3V~ 26V O/P IC U102 Rated 3V~ 32V AUX IC U300 Rated 0V~50V	AC ON/OFF I/P:High-Line +3V =308 V O/P(1)Full Load (2) Output Short (3)O.L.P (4)O.V.P. (5)No Load VR min (Low Line) Ta:25°C	U2 (1) 13.5V (2) 13.7V (3) 13.5V (4) 13.5V (5) 13.5V U1 (1) 13.5V (2) 13.7V (3) 13.5V (4) 13.5V (5) 13.5V



				U102 (1) 10.9V (2) 10.9V (3) 10.9V (4) 10.9V (5) 10.9V U300 (1) 13.5V (2) 13.7V (3) 13.5V (4) 13.5V (5) 13.5V
7	TOP SWITCHING STAND BY POWER	U300 Rated 1 A/ 730V	AC ON/OFF I/P:High-Line +3V =308V O/P: (1)Full Load (2)Remote On/Off I/P:Low-Line -3V =177 V O/P: (1)Full Load (2)Remote On/Off Ta:25°C	308V (1) 539 V (2) 523V 177V (1) 515V (2) 523V

■ SAFETY& E.M.C. TEST

SAFETY TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT
1	WITHSTAND VOLTAGE	I/P-O/P: 4.2 K VAC/min I/P-FG : 2.1 K VAC/min O/P-FG: 1.25 KVAC/min	I/P-O/P: 4.62 KVAC/min I/P-FG: 2.52 KVAC/min O/P-FG: 1.5 KVAC/min Ta:25°C	I/P - O / P: 2.68 mA I / P - F G : 2.73 mA O / P - F G : 2.48 m A NO DAMAGE
2	ISOLATION RESISTANCE	I/P-O/P: 500 VDC>100MΩ I / P - F G : 500 VDC>100MΩ O/P-FG: 500 VDC >100MΩ	I/P-O/P: 500 VDC I / P - F G : 500 VDC O/P-FG: 500 VDC Ta:25°C	I/P - O / P: >9999 MΩ I / P - F G : >9999 MΩ O / P - F G : >9999 MΩ NO DAMAGE
3	GROUNDING CONTINUITY	FG(PE) TO CHASSIS OR TRACE < 100 mΩ	40A / 2min Ta:25°C	11mΩ

E.M.C TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT
1	HARMONIC	EN61000-3-2 CLASS C	I/P:230VAC/50HZ O/P:FULL LOAD Ta:25°C	PASS
2	CONDUCTION	EN55032 CLASS A	I/P : 230 VAC (50HZ) O/P : FULL/50% LOAD Ta : 25°C	PASS Test by certified Lab
3	RADIATION	EN55032 CLASS A	I/P : 230 VAC (50HZ) O/P : FULL LOAD Ta : 25°C	PASS Test by certified Lab
4	E.S.D	EN61000-4-2 AIR : 8KV / Contact : 4KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A
5	E.F.T	EN61000-4-4 INPUT : 2KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A
6	SURGE	EN61000-6-2 L-N : 2KV L,N-PE : 4KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A
7	Test by certified Lab & Test Report Prepare Any contradictions of the test results, please refer to the latest EMC test report			

■ RELIABILITY TEST

ENVIRONMENT TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT																																																																																																																																
1	TEMPERATURE RISE TEST	MODEL : LRS-1200-12 1. ROOM AMBIENT BURN-IN : 2HRS I/P : 230VAC O/P : FULL LOAD Ta= 32.7°C 2. HIGH AMBIENT BURN-IN : 2HRS I/P : 230VAC O/P : FULL LOAD Ta= 48.6°C																																																																																																																																		
		<table><tr><th>NO</th><th>Position</th><th>ROOM AMBIENT Ta=32.7°C</th><th>HIGH AMBIENT Ta=48.6 °C</th></tr><tr><td>1</td><td>RTH1</td><td>40.0°C</td><td>56.1°C</td></tr><tr><td>2</td><td>BD1</td><td>80.3°C</td><td>96.0°C</td></tr><tr><td>3</td><td>Q1</td><td>71.3°C</td><td>88.1°C</td></tr><tr><td>4</td><td>D3</td><td>68.2°C</td><td>85.1°C</td></tr><tr><td>5</td><td>L1</td><td>72.5°C</td><td>88.8°C</td></tr><tr><td>6</td><td>U1</td><td>53.2°C</td><td>69.6°C</td></tr><tr><td>7</td><td>U2</td><td>53.6°C</td><td>71.7°C</td></tr><tr><td>8</td><td>C6</td><td>49.8°C</td><td>66.6°C</td></tr><tr><td>9</td><td>L3</td><td>61.1°C</td><td>80.8°C</td></tr><tr><td>10</td><td>Q3</td><td>64.5°C</td><td>84.9°C</td></tr><tr><td>11</td><td>Q4</td><td>69.4°C</td><td>91.0°C</td></tr><tr><td>12</td><td>C94</td><td>54.5°C</td><td>73.3°C</td></tr><tr><td>13</td><td>T1</td><td>75.7°C</td><td>97.4°C</td></tr><tr><td>14</td><td>T2</td><td>57.0°C</td><td>75.9°C</td></tr><tr><td>15</td><td>U300</td><td>60.7°C</td><td>77.0°C</td></tr><tr><td>16</td><td>C321</td><td>56.1°C</td><td>73.5°C</td></tr><tr><td>17</td><td>C403</td><td>53.6°C</td><td>72.6°C</td></tr><tr><td>18</td><td>C104</td><td>78.2°C</td><td>93.7°C</td></tr><tr><td>19</td><td>U100</td><td>89.3°C</td><td>102.1°C</td></tr><tr><td>20</td><td>U101</td><td>55.5°C</td><td>73.5°C</td></tr><tr><td>21</td><td>U102</td><td>59.5°C</td><td>76.8°C</td></tr><tr><td>22</td><td>Q101</td><td>88.1°C</td><td>105.5°C</td></tr><tr><td>23</td><td>Q104</td><td>91.6°C</td><td>106.1°C</td></tr><tr><td>24</td><td>R125</td><td>87.5°C</td><td>104.3°C</td></tr><tr><td>25</td><td>J112</td><td>87.8°C</td><td>103.7°C</td></tr><tr><td>26</td><td>C111</td><td>72.7°C</td><td>90.2°C</td></tr><tr><td>27</td><td>C106</td><td>69.5°C</td><td>86.4°C</td></tr><tr><td>28</td><td>C114</td><td>59.7°C</td><td>78.5°C</td></tr><tr><td>29</td><td>RTH3</td><td>67.3°C</td><td>85.2°C</td></tr><tr><td>30</td><td>RTH4</td><td>65.1°C</td><td>82.4°C</td></tr><tr><td>31</td><td>TC</td><td>58.8°C</td><td>77.9°C</td></tr></table>			NO	Position	ROOM AMBIENT Ta=32.7°C	HIGH AMBIENT Ta=48.6 °C	1	RTH1	40.0°C	56.1°C	2	BD1	80.3°C	96.0°C	3	Q1	71.3°C	88.1°C	4	D3	68.2°C	85.1°C	5	L1	72.5°C	88.8°C	6	U1	53.2°C	69.6°C	7	U2	53.6°C	71.7°C	8	C6	49.8°C	66.6°C	9	L3	61.1°C	80.8°C	10	Q3	64.5°C	84.9°C	11	Q4	69.4°C	91.0°C	12	C94	54.5°C	73.3°C	13	T1	75.7°C	97.4°C	14	T2	57.0°C	75.9°C	15	U300	60.7°C	77.0°C	16	C321	56.1°C	73.5°C	17	C403	53.6°C	72.6°C	18	C104	78.2°C	93.7°C	19	U100	89.3°C	102.1°C	20	U101	55.5°C	73.5°C	21	U102	59.5°C	76.8°C	22	Q101	88.1°C	105.5°C	23	Q104	91.6°C	106.1°C	24	R125	87.5°C	104.3°C	25	J112	87.8°C	103.7°C	26	C111	72.7°C	90.2°C	27	C106	69.5°C	86.4°C	28	C114	59.7°C	78.5°C	29	RTH3	67.3°C	85.2°C	30	RTH4	65.1°C	82.4°C	31	TC	58.8°C	77.9°C
NO	Position	ROOM AMBIENT Ta=32.7°C	HIGH AMBIENT Ta=48.6 °C																																																																																																																																	
1	RTH1	40.0°C	56.1°C																																																																																																																																	
2	BD1	80.3°C	96.0°C																																																																																																																																	
3	Q1	71.3°C	88.1°C																																																																																																																																	
4	D3	68.2°C	85.1°C																																																																																																																																	
5	L1	72.5°C	88.8°C																																																																																																																																	
6	U1	53.2°C	69.6°C																																																																																																																																	
7	U2	53.6°C	71.7°C																																																																																																																																	
8	C6	49.8°C	66.6°C																																																																																																																																	
9	L3	61.1°C	80.8°C																																																																																																																																	
10	Q3	64.5°C	84.9°C																																																																																																																																	
11	Q4	69.4°C	91.0°C																																																																																																																																	
12	C94	54.5°C	73.3°C																																																																																																																																	
13	T1	75.7°C	97.4°C																																																																																																																																	
14	T2	57.0°C	75.9°C																																																																																																																																	
15	U300	60.7°C	77.0°C																																																																																																																																	
16	C321	56.1°C	73.5°C																																																																																																																																	
17	C403	53.6°C	72.6°C																																																																																																																																	
18	C104	78.2°C	93.7°C																																																																																																																																	
19	U100	89.3°C	102.1°C																																																																																																																																	
20	U101	55.5°C	73.5°C																																																																																																																																	
21	U102	59.5°C	76.8°C																																																																																																																																	
22	Q101	88.1°C	105.5°C																																																																																																																																	
23	Q104	91.6°C	106.1°C																																																																																																																																	
24	R125	87.5°C	104.3°C																																																																																																																																	
25	J112	87.8°C	103.7°C																																																																																																																																	
26	C111	72.7°C	90.2°C																																																																																																																																	
27	C106	69.5°C	86.4°C																																																																																																																																	
28	C114	59.7°C	78.5°C																																																																																																																																	
29	RTH3	67.3°C	85.2°C																																																																																																																																	
30	RTH4	65.1°C	82.4°C																																																																																																																																	
31	TC	58.8°C	77.9°C																																																																																																																																	

2	OVER LOAD BURN-IN TEST	NO DAMAGE 1 HOUR (MIN)	I/P : 230 VAC O/P : 115 % LOAD Ta : 25°C	TEST : OK
3	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 2 HOUR	I/P : 305VAC/200VAC O/P : 100 % LOAD Ta=-35 °C	TEST : OK
4	HIGH HUMIDITY HIGH TEMPERATURE HIGH VOLTAGE TURN ON TEST	AFTER 12 HOURS IN CHAMBER ON CONTROL 50 °C/95 %R.H NO DAMAGE	I/P : 315 VAC O/P : FULL LOAD Ta= 50 °C HUMIDITY= 95 %R.H	TEST : OK
5	TEMPERATURE COEFFICIENT	± 0.03 %/°C(0~30°C)	I/P : 230 VAC O/P : FULL LOAD	± 0.0048 %/°C(0~30°C)
6	STORAGE TEMPERATURE TEST	-40~85°C	1. Thermal shock Temperature : -45°C~ +90°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 10 CYCLE 5. Input/output condition : STATIC	
7	THERMAL SHOCK TEST	-30~45°C	1. Thermal shock Temperature : -35°C~ +50°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 16 CYCLE 5. Input/output condition : 15cycle:230V/ FULL LOAD AC ON 3sec/AC OFF 1sec TEST 1cycle:230V/ FULL LOAD Burn In Test	
8	VIBRATION TEST	10 ~ 500Hz, 3G 10min./1cycle, 60min. each along X, Y, Z axes	1 Carton & 1 Set (1) Waveform : Sine Wave (2) Frequency : 10~500Hz (3) Sweep Time : 10min/sweep cycle (4) Acceleration : 4G (5) Test Time : 180min in each axis (X.Y.Z) (6) Ta : 25°C	
9	CAPACITOR LIFE CYCLE	SUPPOSE C111 IS THE MOST CRITICAL COMPONENT (1) I/P : 230VAC O/P : FULL LOAD Ta=25 °C LIFE TIME (2) I/P : 230VAC O/P : FULL LOAD Ta=45 °C LIFE TIME (3) I/P : 230VAC O/P : 75% LOAD Ta=45 °C LIFE TIME (4) I/P : 230VAC O/P : 50% LOAD Ta=45 °C LIFE TIME	(1) 500000HRS (2) 41588HRS (3) 284426HRS (4) 1199416HRS	
10	MTBF	Conducted by Parts Stress Analysis Prediction 924.6K hrs min. Telcordia SR-332 (Bellcore) ; 93.2K hrs min. MIL-HDBK-217F (25°C)		
11	Ongoing Reliability Test	I/P : 230VAC O/P : FULL LOAD TA=50°C Demonstration Mean Time Between Failure : 30,000 hours		

TEST RESULT	TESTER	REVIEW	APPROVAL
PASS	WUWQIN/ZHOUBIAO	WENF	WUWQ

2020.10.1 TAG-QA-009